ENVIRONMENTAL PROTECTION – LIST OF SCHEMES

MARCH 2010

Ward	Location	Scheme	Works to be undertaken	
			March 2010 - Sept. 2010	Oct. 2010 - March 2011
Haydock	Highway Maintenance Schemes			
	A599 Penny Lane – Parts	Carriageway Resurfacing	✓	
	A599 Clipsley Lane – Parts	Carriageway Resurfacing	✓	
	Central Drive (Parts)	Micro Asphalt	✓	
	Wagon Lane (Clipsley Lane to Windermere Avenue)	Micro Asphalt	✓	
	Other Highway Schemes			
	A49	Environmental Improvements	✓	
	Traffic Schemes			
	M6/A580/A49 Intersection including Ashton Road and Lodge Lane	Reduction of speed limits from derestricted/60 mph to 40 mph, inclusive of signing and lining enhancements. Ongoing	✓	
	Lighting Schemes			
	King George V Playing Fields	Floodlighting/Mosquito Buzzer to Play Area (awaiting electricity services)	✓	

ENVIRONMENTAL PROTECTION – LIST OF SCHEMES

MARCH 2010

Ward	Location	Scheme	Works to be undertaken	
			March 2010 - Sept. 2010	Oct. 2010 - March 2011
Haydock (Cont'd)	Civic Spaces Schemes Pride & Community			
	King George V Playing Fields	Playbuilder Project subject to Consultation and Planning	✓	

Carriageway Resurfacing Scheme

In a carriageway resurfacing scheme the top layers of the road surface will be removed. Manhole covers and gully grates and frames will be set to new levels. The road surface will be regulated if required, and a new surface course will be laid. Road markings will be replaced on completion of the works.

Carriageway resurfacing is undertaken when the road surface has become cracked, rutted or has started to break up. The new surface protects the underlying layers from water penetration, strengthens the road construction and provides an improved ride quality for vehicles.

Micro Asphalt

This is similar to carriageway sealing with a larger aggregate and is used as an intermediate process when the road condition is too poor to use slurry seal but not bad enough to warrant resurfacing.